BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/06/12-13 Date: 11.02.2013 Item No: 11

SCHEDULE-B

NAME OF WORK:Improvement to roads & drains at Abbigere Ganesha Temple, in Ward no. 12, in Shettyhalli Sub-Division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **ASWATHNARAYAN ANJANAPPA**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	142.10	100.0	Rupees One Hundred Only
2	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed complete as per specifications.	Cum	457.83	123.0	Rupees One Hundred Twenty Three Only
3	Providing Granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc. complete as per specifications.	Sqm	1177.20	345.0	Rupees Three Hundred Forty Five Only
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density Complete as per Specification. A. By manual means. MORTH Specification No. 404 Type A 13.2mm for grading II	Cum	228.92	1000.0	Rupees One Thousand Only
5	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Complete as per Specification. B. By Mechanical means. MORTH Specification No. 404 Type B 11.2mm for grading III	Cum	152.61	1200.0	Rupees One Thousand Two Hundred Only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading, complete as per specifications.	Cum	399.93	100.0	Rupees One Hundred Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division.